RATES SCHEDULE NM—NET METERING

AVAILABILITY OF NET METERING SERVICE

Net Metering is available to eligible member-generators in Cumberland Valley Electric's service territory, upon request, and on a first-come, first-served basis up to a cumulative capacity of one percent (1%) of the Cumberland Valley Electric's single hour peak load during the previous year. If the cumulative generating capacity of net metering systems reaches 1% of a supplier's single hour peak load during the previous year, upon Commission approval, Cumberland Valley Electric's obligation to offer net metering to a new member-generator may be limited. An eligible member-generator shall mean a member retail electric member of Cumberland Valley Electric with a generating facility that:

- 1) Generates electricity using solar energy, wind energy, biomass or biogas energy, or hydro energy;
- 2) Has a rated capacity of not greater than thirty (30) kilowatts;
- 3) Is located on the member's premises;
- 4) Is owned and operated by the member;
- 5) Is connected in parallel with Cumberland Valley Electric's electric distribution system; and
- 6) Has the primary purpose of supplying all or part of the member's own electricity requirements.
- At its sole discretion, Cumberland Valley Electric may provide Net Metering to other membergenerators not meeting all the conditions listed above on a case-by-case basis.

METERING

Cumberland Valley Electric shall provide net metering services, without any cost to the Member for metering equipment, through a standard kilowatt-hour metering system capable of measuring the flow of electricity in two (2) directions. This provision does not relieve Member of his or her responsibility to pay metering costs embedded in the Cumberland Valley Electric's Commission-

	PUBLIC SERVICE COMMISSION OF KENTUCKY EFFECTIVE
DATE OF ISSUE <u>April 2, 2009</u> , DATE EFFECTIVE: <u>April 8, 200</u> ISSUED BY <u>Led Hangton</u> TITLE <u>Pres</u>	PURSUANT TO 807 KAR 5:011
Issued by authority of an Order of the Public Service Commission Case No. 2008-00169 Dated January 8, 2009	By Executive Director

	FOR ENTIRE TERRITORY SERVED
	P.S.C
Cumberland Valley Electric	Original Sheet No.

approved base rates. Net metered electricity shall be measured in accordance with standard metering practices established by Cumberland Valley Electric using metering equipment capable of measuring and recording energy flows, on a kWh basis, from Cumberland Valley Electric to the member-generator and from the member-generator to Cumberland Valley Electric, with each directional energy flow recorded independently. If time-of-day or time-of-use metering is used, the electricity fed back to the electric grid by the member-generator shall be metered and accounted for at the specific time it is fed back to the electric grid in accordance with the time-of-day and time-of-use billing agreement currently in place.

Any additional meter, meters, or distribution upgrades needed to monitor the flow in each direction shall be installed at the Member's expense.

BILLING AND PAYMENT

For charges collected on the basis of metered registration, Cumberland Valley Electric shall, for each monthly billing period, determine the net meter registration of the member-generator by comparing the directional energy flow in each direction. If the net meter registration shows that the deliveries of energy in kWh from the member-generator to Cumberland Valley Electric exceed the deliveries of energy in kWh from Cumberland Valley Electric to the membergenerator, the net meter registration in kWh will be carried forward to the next monthly billing period as a Net Metering Credit, expressed in kWh. If the member-generators carried over a Net Metering Credit from one of more prior months, the net meter registration from the current month shall be added to the Net Metering Credit that exists from prior months.

If the net metering registration shows that deliveries of energy in kWh from the Cooperative to the member-generator exceed the deliveries of energy in kWh from the member-generator to the Cooperative, the member-generator shall pay the Cooperative for the net amount of energy delivered by the Cooperative after application of any Net Metering Credit carried forward from previous months at the current rate applicable to its type or class of electric service.

The member shall be responsible for payment of any applicable member charge or other applicable charges.

At no time shall Cumberland Valley Electric be required to convert the Net Billing Credit to cash. If a member-generator closes his account, no cash refund for residual Net Metering Credits shall be paid.

Net Metering Credits are not transferable between members	DI PORSION SERVICE COMMISSION OF KENTUCKY
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009 ISSUED BY	
Issued by authority of an Order of the Public Service Commission Case No. 2008-00169 Dated January 8, 2009	

APPLICATION AND APPROVAL PROCESS

The Member shall submit an Application for Interconnection and Net Metering ("Application") and receive approval from Cumberland Valley Electric prior to connecting the generator facility to Cumberland Valley Electric's system.

Applications will be submitted by the Member and reviewed and processed by Cumberland Valley Electric according to either Level 1 or Level 2 processes defined in this tariff.

Cumberland Valley Electric may reject an Application for violations of any code, standard, or regulation related to reliability or safety; however, Cumberland Valley Electric will work with the Member to resolve those issues to the extent practicable.

Members may contact Cumberland Valley Electric to check on status of an Application or with questions prior to submitting an Application. Contact information is provided on the Application form and is listed on Cumberland Valley Electric's website.

LEVEL 1 AND LEVEL 2 DEFINITIONS

LEVEL 1

A Level 1 Application shall be used if the generating facility is inverter-based and is certified by a nationally recognized testing laboratory to meet the requirements of Underwriters Laboratories Standard 1741 "Inverters, Converters, Controllers and Interconnection System Equipment for Use With Distributed Energy Resources" (UL 1741).

Cumberland Valley Electric will approve the Level 1 Application if the generating facility also meets all of the following conditions:

 For interconnection to a radial distribution circuit, the aggregated generation on the circuit, including the proposed generating facility, will not exceed 15% of the Line Section's most recent annual one hour peak load. A line section is the smallest part of the primary distribution system the generating facility could remain connected to after operation of any sectionalizing devices.

	PUBLIC SERVICE COMMISSION OF KENTUCKY
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	EFFECTIVE
PCIL	4/8/2009
ISSUED BY TITLE Pres	dent & RUMESUEA BOUTIVE 80 File Ar 5:011
e ili que	SECTION 9 (1)
Issued by authority of an Order of the Public Service Commission Case No. 2008-00169 Dated January 8, 2009	of] By H Deeve Executive Director

·	FOR ENTIRE	E TERRITORY SERV	VED
		P.S.C.	
		Original Sheet No.	

- 2) If the proposed generating facility is to be interconnected on a single-phase shared secondary, the aggregate generation capacity, including the proposed generating facility, will not exceed the smaller of 20 kVA or the nameplate rating of the transformer.
- 3) If the proposed generating facility is single-phase and is to be interconnected on a center tap neutral of a 240 volt service, its addition shall not create an imbalance between the two sides of the 240 volt service of more than 20% of the nameplate rating of the service transformer.
- 4) If the generating facility is to be connected to three-phase, three wire primary Cumberland Valley Electric distribution lines, the generator shall appear as a phaseto-phase connection at the primary Cumberland Valley Electric distribution line.
- 5) If the generating facility is to be connected to three-phase, four wire primary Cumberland Valley Electric distribution lines, the generator shall appear to the primary Cumberland Valley Electric distribution line as an effectively grounded source.
- 6) The interconnection will not be on an area or spot network.

- 7) Cumberland Valley Electric does not identify any violations of any applicable provisions of IEEE 1547, "Standard for Interconnecting Distributed Resources with Electric Power Systems."
- 8) No construction of facilities by Cumberland Valley Electric on its own system will be required to accommodate the generating facility.

If the generating facility does not meet all of the above listed criteria, Cumberland Valley Electric, in its sole discretion, may either: 1) approve the generating facility under the Level 1 Application if Cumberland Valley Electric determines that the generating facility can be safely and reliably connected to Cumberland Valley Electric's system; or 2) deny the Application as submitted under the Level 1 Application.

Cumberland Valley Electric shall notify the member within 20 business days whether the Application is approved or denied, based on the criteria provided in this section.

11 11	
	PUBLIC SERVICE COMMISSION OF KENTUCKY
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	
	4/8/2009
ISSUED BY Jed Junster TITLE Presi	dent & CHREFEREUTIVE OFFICER 5:011
4	SECTION 9 (1)
Issued by authority of an Order of the Public Service Commission Case No. 2008-00169 Dated January 8, 2009	of I By By Executive Director

	• • •	FOR ENTIRE TERRITORY SERVED
		P.S.C
Cumberland Valley Electric		Original Sheet No.

If the Application lacks complete information, Cumberland Valley Electric shall notify the Member that additional information is required, including a list of such additional information. The time between notification and receipt of required additional information will add to the time to process the Application.

When approved, Cumberland Valley Electric will indicate by signing the approval line on the Level 1 Application Form and returning it to the Member. The approval will be subject to successful completion of an initial installation inspection and witness test if required by Cumberland Valley Electric. Cumberland Valley Electric's approval section of the Application will indicate if an inspection and witness test are required. If so, the Member shall notify Cumberland Valley Electric within 3 business days of completion of the generating facility installation and schedule an inspection and witness test with Cumberland Valley Electric to occur within 10 business days of completion of the generator facility installation or as otherwise agreed to by Cumberland Valley Electric and the Member. The Member may not operate the generating facility until successful completion of such inspection and witness test, unless Cumberland Valley Electric expressly permits operational testing not to exceed two hours. If the installation fails the inspection or witness test due to non-compliance with any provision in the Application and Cumberland Valley Electric approval, the Member shall not operate the generating facility until any and all non-compliance issues are corrected and re-inspected by Cumberland Valley Electric.

If the Application is denied, Cumberland Valley Electric will supply the Member with reasons for denial. The Member may resubmit under Level 2 if appropriate.

LEVEL 2

A Level 2 Application is required under any of the following:

- 1) The generating facility is not inverter based;
- 2) The generating facility uses equipment that is not certified by a nationally recognized testing laboratory to meet the requirements of UL 1741; or
- 3) The generating facility does not meet one or more of the additional conditions under Level 1.

	PUBLIC SERVICE COMMISSION OF KENTUCKY EFFECTIVE
DATE OF ISSUE <u>April 2, 2009</u> , DATE EFFECTIVE: <u>April 8, 2009</u> ISSUED BY <u>Leck Hupton</u> TITLE <u>Presi</u>	4/8/2009 PURSUANT TO 807 KAR 5:011 dent & Chief Executive Mariler
Issued by authority of an Order of the Public Service Commission Case No. 2008-00169 Dated January 8, 2009	of] By Executive Director

FOR ENTIRE TERRITORY SERVED

Cumberland Valley Electric

دن ^{ر.}

Original Sheet No.

P.S.C.

Cumberland Valley Electric will approve the Level 2 Application if the generating facility meets Cumberland Valley Electric's technical interconnection requirements, which are based on IEEE 1547.

Cumberland Valley Electric will process the Level 2 Application within 30 business days of receipt of a complete Application. Within that time Cumberland Valley Electric will respond in one of the following ways:

- 1) The Application is approved and Cumberland Valley Electric will provide the Member with an Interconnection Agreement to sign.
- 2) If construction or other changes to Cumberland Valley Electric's distribution system are required, the cost will be the responsibility of the Member. Cumberland Valley Electric will give notice to the Member and offer to meet to discuss estimated costs and construction timeframe. Should the Member agree to pay for costs and proceed, Cumberland Valley Electric will provide the Member with an Interconnection Agreement to sign within a reasonable time.
- 3) The Application is denied. Cumberland Valley Electric will supply the Member with reasons for denial and offer to meet to discuss possible changes that would result in Cumberland Valley Electric approval. Member may resubmit Application with changes.

If the Application lacks complete information, Cumberland Valley Electric shall notify the Member that additional information is required, including a list of such additional information. The time between notification and receipt of required additional information will add to the 30-business-day target to process the Application.

The Interconnection Agreement will contain all the terms and conditions for interconnection consistent with those specified in this tariff, inspection and witness test requirements, description of and cost of construction or other changes to Cumberland Valley Electric's distribution system required to accommodate the generating facility, and detailed documentation of the generating facilities which may include single line diagrams, relay settings, and a description of operation.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE
dent & Chief Executive Officer
PURSUANT TO 807 KAR 5:011
of Kentucky in SECTION 9 (1)
By W Deem Executive Director

 $e^{i\lambda_{1}i\gamma}$

.

The Member may not operate the generating facility until an Interconnection Agreement is signed by the Member and Cumberland Valley Electric and all necessary conditions stipulated in the agreement are met.

APPLICATION, INSPECTION AND PROCESSING FEES

No application fees or other review, study, or inspection or witness test fees may be charged by Cumberland Valley Electric for Level 1 Applications.

Cumberland Valley Electric requires each Member to submit with each Level 2 Application a non-refundable application, inspection and processing fee of **\$100** for Level 2 Applications. In the event Cumberland Valley Electric determines an impact study is necessary with respect to a Level 2 Application, the Member shall be responsible for any reasonable costs up to \$1,000 for the initial impact study. Cumberland Valley Electric shall provide documentation of the actual cost of the impact study. Any other studies requested by the Member shall be at the Member's sole expense.

TERMS AND CONDITIONS FOR INTERCONNECTION

To interconnect to Cumberland Valley Electric's distribution system, the Member's generating facility shall comply with the following terms and conditions:


- Cumberland Valley Electric shall provide the Member net metering services, without charge for standard metering equipment, through a standard kilowatt-hour metering system capable of measuring the flow of electricity in two (2) directions. If the Member requests any additional meter or meters or distribution upgrades are needed to monitor the flow in each direction, such installations shall be at the Member's expense.
- 2) The Member shall install, operate, and maintain, at Member's sole cost and expense, any control, protective, or other equipment on the Member's system required by Cumberland Valley Electric's technical interconnection requirements based on IEEE 1547, the NEC, accredited testing laboratories such as Underwriters Laboratories, and the manufacturer's suggested practices for safe, efficient and reliable operation

PUBLIC SERVICE COMMISSION OF KENTUCKY
EFFECTIVE
4/8/2009
ident & Chief Executive Officer 5:011
SECTION 9 (1)
$n \text{ of } M \cap Q$
Will Wanny
By M Langer
V Executive Director

· · · ·	FOR ENTIRE TERRITORY SERVED
	P.S.C
Cumberland Valley Electric	Original Sheet No.

of the generating facility in parallel with Cumberland Valley Electric's electric system. Member shall bear full responsibility for the installation, maintenance and safe operation of the generating facility. Upon reasonable request from Cumberland Valley Electric, the Member shall demonstrate generating facility compliance.

- 3) The generating facility shall comply with, and the Member shall represent and warrant its compliance with: (a) any applicable safety and power quality standards established by IEEE and accredited testing laboratories such as Underwriters Laboratories; (b) the NEC as may be revised from time to time; (c) Cumberland Valley Electric's rules, regulations, and Service Regulations as contained in Cumberland Valley Electric's Retail Electric Tariff as may be revised from time to time with the approval of the Kentucky Public Service Commission (Commission); (d) the rules and regulations of the Commission, as such rules and regulations may be revised from time to time to time to time to time by the Commission; and (e) all other applicable local, state, and federal codes and laws, as the same may be in effect from time to time. Where required by law, Member shall pass an electrical inspection of the generating facility by a local authority having jurisdiction over the installation.
- 4) Any changes or additions to Cumberland Valley Electric's system required to accommodate the generating facility shall be considered excess facilities. Member shall agree to pay Cumberland Valley Electric for actual costs incurred for all such excess facilities prior to construction.
- 5) Member shall operate the generating facility in such a manner as not to cause undue fluctuations in voltage, intermittent load characteristics or otherwise interfere with the operation of Cumberland Valley Electric's electric system. At all times when the generating facility is being operated in parallel with Cumberland Valley Electric's electric's electric system, Member shall operate the generating facility in such a manner that no adverse impacts will be produced thereby to the service quality rendered by Cumberland Valley Electric to any of its other members or to any electric system interconnected with Cumberland Valley Electric's electric's electric system. Member shall agree that the interconnection and operation of the generating facility is secondary to, and shall not interfere with, Cumberland Valley Electric's ability to meet its primary responsibility of furnishing reasonably adequate service to its members.



·· · ·		FOR ENTIRE TERRITORY SERVED
		P.S.C
Cumberland V	/alley Electric	 Original Sheet No.

- 6) The Member shall be responsible for protecting, at Member's sole cost and expense, the generating facility from any condition or disturbance on Cumberland Valley Electric's electric system, including, but not limited to, voltage sags or swells, system faults, outages, loss of a single phase of supply, equipment failures, and lightning or switching surges, except that Cumberland Valley Electric shall be responsible for repair of damage caused to the generating facility resulting solely from the negligence or willful misconduct on the part of Cumberland Valley Electric.
- 7) After initial installation, Cumberland Valley Electric shall have the right to inspect and/or witness commissioning tests, as specified in the Level 1 or Level 2 Application and approval process. Following the initial testing and inspection of the generating facility and upon reasonable advance notice to the Member, Cumberland Valley Electric shall have access at reasonable times to the generating facility to perform reasonable on-site inspections to verify that the installation, maintenance, and operation of the generating facility comply with the requirements of this tariff.
- 8) For Level 1 and 2 generating facilities, an eligible Member shall furnish and install on the Member's side of the point of common coupling a safety disconnect switch which shall be capable of fully disconnecting the Member's energy generating the equipment from Cumberland Valley Electric's electric service under the full rated conditions of the Member's generating facility. The external disconnect switch (EDS) shall be located adjacent to Cumberland Valley Electric's meters or the location of the EDS shall be noted by placing a sticker on the meter, and shall be of the visible break type in a metal enclosure which can be secured by a padlock. If the EDS is not located directly adjacent to the meter, the Member shall be responsible for ensuring that the location of the EDS is properly and legibly identified for so long as the generating facility is operational. The disconnect switch shall be accessible to Cumberland Valley Electric personnel at all times. Cumberland Valley Electric may waive the requirement for an EDS for a generating facility at its sole discretion, and on a case-by-case basis, upon review of the generating facility . operating parameters and if permitted under Cumberland Valley Electric's safety and operating protocols.
- 9) Cumberland Valley Electric shall have the right and authority at [Name of Cooperative's] sole discretion to isolate the generating facility or require the Member to discontinue operation of the generating facility if Name ef COMMISSION

	OF KENTUCKY	
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 200	EFFECTIVE	
	4/8/2009	
ISSUED BY Led Hangton TITLE Pres	dent & CHRETEXNETUTIOe 807 ft 64 F 5:011	
0	SECTION 9 (1)	
Issued by authority of an Order of the Public Service Commissio	of $M \cap Q$	
Case No. 2008-00169 Dated January 8, 2009		
	By M Andew	
	Executive Director	

	FOR ENTIRE TERRITORY SERVED
•	P.S.C
Cumberland Valley Electric	Original Sheet No.

Cooperative] believes that: (a) continued interconnection and parallel operation of the generating facility with Cumberland Valley Electric's electric system may create or contribute to a system emergency on either Cumberland Valley Electric's or the Member's electric system; (b) the generating facility is not in compliance with the requirements of this tariff, and the noncompliance adversely affects the safety, reliability, or power quality of Cumberland Valley Electric's electric system; or (c) the generating facility interferes with the operation of Cumberland Valley Electric's electric system. In non-emergency situations, Cumberland Valley Electric shall give the Member notice of noncompliance including a description of the specific noncompliance condition and allow the Member a reasonable time to cure the noncompliance prior to isolating the generating facilities. In emergency situations, when Cumberland Valley Electric is unable to immediately isolate or cause the Member to isolate only the generating facility, Cumberland Valley Electric may isolate the Member's entire facility.

- 10) The Member shall agree that, without the prior written permission from Cumberland Valley Electric, no changes shall be made to the generating facility as initially approved. Increases in generating facility capacity will require a new "Application for Interconnection and Net Metering" which will be evaluated on the same basis as any other new application. Repair and replacement of existing generating facility components with like components that meet UL 1741 certification requirements for Level 1 facilities and not resulting in increases in generating facility capacity is allowed without approval.
- 11) To the extent permitted by law, the Member shall protect, indemnify, and hold harmless the Cumberland Valley Electric and its directors, officers, employees, agents, representatives and contractors against and from all loss, claims, actions or suits, including costs and attorneys fees, for or on account of any injury or death of persons or damage to property caused by the Member or the Member's employees, agents, representatives and contractors in tampering with, repairing, maintaining, or operating the Member's generating facility or any related equipment or any facilities owned by Cumberland Valley Electric except where such injury, death or damage was caused or contributed to by the fault or negligence of Cumberland Valley Electric or its employees, agents, representatives, or contractors.

	PUBLIC SERVICE COMMISSION OF KENTUCKY
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	EFFECTIVE
	4/8/2009
ISSUED BY Les that TITLE Presi	dent & PURSEALUTICE OFTIKAR 5:011
	SECTION 9 (1)
Issued by authority of an Order of the Public Service Commissior Case No. 2008-00169 Dated January 8, 2009	of I By H Deere Executive Director

The liability of Cumberland Valley Electric to the Member for injury to person and property shall be governed by the tariff(s) for the class of service under which the Member is taking service.

- 12) The Member shall maintain general liability insurance coverage (through a standard homeowner's, commercial, or other policy) for both Level 1 and Level 2 generating facilities. The Member shall, upon request, provide Cumberland Valley Electric with proof of such insurance at the time that application is made for net metering.
- 13) By entering into an Interconnection Agreement, or by inspection, if any, or by nonrejection, or by approval, or in any other way, Cumberland Valley Electric does not give any warranty, express or implied, as to the adequacy, safety, compliance with applicable codes or requirements, or as to any other characteristics, of the generating facility equipment, controls, and protective relays and equipment.
- 14) A Member's generating facility is transferable to other persons or service locations only after notification to Cumberland Valley Electric has been made and verification that the installation is in compliance with this tariff. Upon written notification that an approved generating facility is being transferred to another person, member, or location, Cumberland Valley Electric will' verify that the installation is in compliance with this tariff and provide written notification to the member(s) within 20 business days. If the installation is no longer in compliance with this tariff, Cumberland Valley Electric will notify the Member in writing and list what must be done to place the facility in compliance.
- 15) The Member shall retain any and all Renewable Energy Credits (RECs) that may be generated by their generating facility.

EFFECTIVE TERM AND TERMINATION RIGHTS

This Agreement becomes effective when executed by both parties and shall continue in effect until terminated. This Agreement may be terminated as follows: (a) Member may terminate this Agreement at any time by giving Cumberland Valley Electric at least sixty (60) days' written notice; (b) Cumberland Valley Electric may terminate upon failure by the Member to continue ongoing operation of the generating facility; (c) either party may terminate by giving the other party at

	PUBLIC SERVICE COMMISSION
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	OF KENTUCKY
-1 (1) (-1	EFFECTIVE
ISSUED BY length TITLE Presi	dent & Chief Exectite @ ficer
	PURSUANT TO 807 KAR 5:011
Issued by authority of an Order of the Public Service Commission	of Kentuckv in SECTION 9 (1)
Case No. 2008-00169 Dated January 8, 2009	By W DRocen
	VIII Kecutive Director

least thirty (30) days prior written notice that the other party is in default of any of the terms and conditions of the Agreement or the Rules or any rate schedule, tariff, regulation, contract, or policy of Cumberland Valley Electric, so long as the notice specifies the basis for termination and there is opportunity to cure the default; (d) Cumberland Valley Electric may terminate by giving the Member at least thirty (30) days notice in the event that there is a material change in an applicable law, regulation or statute affecting this Agreement or which renders the system out of compliance with the new law or statute.

Cumberland Valley Electric

	PUBLIC SERVICE COMMISSION
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	
ISSUED BY IIILE Presi	EFFECTIVE dent & Chief Exective Officer PURSUANT TO 807 KAR 5:011
Issued by authority of an Order of the Public Service Commission Case No: <u>2008-00169</u> Dated <u>January 8, 2009</u>	of Kentuckv in SECTION 9 (1) By By Executive Director

FOR ENTIRE TERRITORY SERVED P.S.C.

Cumberland Valley Electric

Original Sheet No.

LEVEL 1

Application for Interconnection and Net Metering

Use this application form only for a generating facility that is inverter based and certified by a nationally recognized testing laboratory to meet the requirements of UL1741.

Submit this Application to:

Cumberland Valley Electric, P.O. Box 440, Gray, KY 40734

If you have questions regarding this Application or its status, contact the Cooperative at:

1-800-513-2677 or contact@cumberlandvalley.coop

Member Name:	Account Number:
Member Address:	
Member PhoneNo.:	Member E-Mail Address:
Project Contact Person:	
Phone No.:	E-mail Address (Optional):
Provide names and contact inf in the design and installation o	formation for other contractors, installers, or engineering firms involved f the generating facilities:
Energy Source: Solar	Wind Hydro Biogas Biomass
Inverter Manufacturer and Mo	del #:
Inverter Power Rating:	Inverter Voltage Rating:
Power Rating of Energy Source	ce (i.e., solar panels, wind turbine):
Is Battery Storage Used:	No Yes If Yes, Battery Power Rating:
	PUBLIC SERVICE COMMISSION
	9, DATE EFFECTIVE: <u>April 8, 200</u> <u>EFFECTIVE</u>
ISSUED BY Led H	4/8/2009 TITLE President & Chief Executive 80 Flick 5:011
	er of the Public Service Commission of SECTION 9 (1)

FOR ENTIRE TERRITORY SERVED P.S.C.

Cumberland Valley Electric

Original Sheet No.

Attach documentation showing that inverter is certified by a nationally recognized testing laboratory to meet the requirements of UL 1741.

Attach site drawing or sketch showing location of Cooperative's meter, energy source, Cooperative accessible disconnect switch and inverter.

Attach single line drawing showing all electrical equipment from the Cooperative's metering location to the energy source including switches, fuses, breakers, panels, transformers, inverters, energy source, wire size, equipment ratings, and transformer connections.

4.14

Expected Start-up Date: _____

. سري د

	PUBLIC SERVICE COMMISSION
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	OF KENTUCKY EFFECTIVE
ISSUED BY Led Hugh TITLE Preside	4/8/2009 lent & Chief Executive Officer PURSUANT TO 807 KAR 5:011
Issued by authority of an Order of the Public Service Commission Case No. 2008-00169 Dated January 8, 2009	of Kentucky in SECTION 9 (1)
Case No. 2008-00109 Dated January 8, 2009	By Il Mour
	Executive Director

TERMS AND CONDITIONS:

- 1) Cumberland Valley Electric shall provide the Member net metering services, without charge for standard metering equipment, through a standard kilowatt-hour metering system capable of measuring the flow of electricity in two (2) directions. If the Member requests any additional meter or meters or distribution upgrades are needed to monitor the flow in each direction, such installations shall be at the Member's expense.
- 2) The Member shall install, operate, and maintain, at Member's sole cost and expense, any control, protective, or other equipment on the Member's system required by Cumberland Valley Electric's technical interconnection requirements based on IEEE 1547, the NEC, accredited testing laboratories such as Underwriters Laboratories, and the manufacturer's suggested practices for safe, efficient and reliable operation of the generating facility in parallel with Cumberland Valley Electric's electric system. The Member shall bear full responsibility for the installation, maintenance and safe operation of the generating facility. Upon reasonable request from Cumberland Valley Electric, the Member shall demonstrate generating facility compliance.
- 3) The generating facility shall comply with, and the Member shall represent and warrant its compliance with: (a) any applicable safety and power quality standards established by IEEE and accredited testing laboratories such as Underwriters Laboratories; (b) the NEC as may be revised from time to time; (c) Cumberland Valley Electric's rules, regulations, and Service Regulations as contained in Cumberland Valley Electric's Retail Electric Tariff as may be revised from time to time with the approval of the Kentucky Public Service Commission (Commission); (d) the rules and regulations of the Commission, as such rules and regulations may be revised from time to time by the Commission; and (e) all other applicable local, state, and federal codes and laws, as the same may be in effect from time to time. Where required by law, Member shall pass an electrical inspection of the generating facility by a local authority having jurisdiction over the installation.
- 4) Any changes or additions to Cumberland Valley Electric's system required to accommodate the generating facility shall be considered excess facilities. Member shall agree to pay Cumberland Valley Electric for actual costs incurred for all such excess facilities prior to construction.

	PUBLIC SERVICE COMMISSION
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	OF KENTUCKY
I () ()	EFFECTIVE
ISSUED BY <u>Icd Hungton</u> TITLE Presi	dent & Chief Exectitive Officer PURSUANT TO 807 KAR 5:011
Issued by authority of an Order of the Public Service Commission	
Case No. 2008-00169 Dated January 8, 2009	By W Director

· · · · ·	FOR ENTIRE TERRITORY SERVED
<i>,</i>	P.S.C
Cumberland Valley Electric	 Original Sheet No.

5) The Member shall operate the generating facility in such a manner as not to cause undue fluctuations in voltage, intermittent load characteristics or otherwise interfere with the operation of Cumberland Valley Electric's electric system. At all times when the generating facility is being operated in parallel with Cumberland Valley Electric's electric system, the Member shall operate the generating facility in such a manner that no adverse impacts will be produced thereby to the service quality rendered by Cumberland Valley Electric to any of its other members or to any electric system interconnected with Cumberland Valley Electric's electric's electric's electric's electric system. The Member shall agree that the interconnection and operation of the generating facility is secondary to, and shall not interfere with, Cumberland Valley Electric's ability to meet its primary responsibility of furnishing reasonably adequate service to its members.

6) The Member shall be responsible for protecting, at Member's sole cost and expense, the generating facility from any condition or disturbance on Cumberland Valley Electric's electric system, including, but not limited to, voltage sags or swells, system faults, outages, loss of a single phase of supply, equipment failures, and lightning or switching surges, except that Cumberland Valley Electric shall be responsible for repair of damage caused to the generating facility resulting solely from the negligence or willful misconduct on the part of Cumberland Valley Electric.

- 7) After initial installation, Cumberland Valley Electric shall have the right to inspect and/or witness commissioning tests, as specified in the Level 1 or Level 2 Application and approval process. Following the initial testing and inspection of the generating facility and upon reasonable advance notice to the Member, Cumberland Valley Electric shall have access at reasonable times to the generating facility to perform reasonable on-site inspections to verify that the installation, maintenance, and operation of the generating facility comply with the requirements of this tariff.
- 8) For Level 1 and 2 generating facilities, an eligible Member shall furnish and install on the Member's side of the point of common coupling a safety disconnect switch which shall be capable of fully disconnecting the Member's energy generating equipment from Cumberland Valley Electric's electric service under the full rated conditions of the Member's generating facility. The external disconnect switch (EDS) shall be located adjacent to Cumberland Valley Electric's meters or the location of the EDS shall be noted by placing a sticker on the meter, and shall be of the visible break type in a metal enclosure which can be secured by a padlock. If the EDS is not located directly adjacent to the meter, the

DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009 PUBLIC SERVICE COMMISSION OF KENTUCKY TITLE President & Chief Executive Officer **ISSUED B** 4/8/2009 Issued by authority of an Order of the Public Service Commission of Kentucks UANT TO 807 KAR 5:011 Case No. 2008-00169 Dated January 8, 2009 SECTION 9(1) Director

- .	FOR ENTIRE TERRITORY SERVED
	P.S.C
Cumberland Valley Electric	Original Sheet No.

Member shall be responsible for ensuring that the location of the EDS is properly and legibly identified for so long as the generating facility is operational. The disconnect switch shall be accessible to Cumberland Valley Electric personnel at all times. Cumberland Valley Electric may waive the requirement for an EDS for a generating facility at its sole discretion, and on a case-by-case basis, upon review of the generating facility operating parameters and if permitted under Cumberland Valley Electric's safety and operating protocols.

- 9) Cumberland Valley Electric shall have the right and authority at Cumberland Valley Electric's sole discretion to isolate the generating facility or require the Member to discontinue operation of the generating facility if Cumberland Valley Electric believes that: (a) continued interconnection and parallel operation of the generating facility with Cumberland Valley Electric's electric system may create or contribute to a system emergency on either Cumberland Valley Electric's or the Member's electric system; (b) the generating facility is not in compliance with the requirements of this tariff, and the noncompliance adversely affects the safety, reliability, or power quality of Cumberland Valley Electric's electric system. In non-emergency situations, Cumberland Valley Electric shall give the Member notice of noncompliance including a description of the specific noncompliance condition and allow the Member a reasonable time to cure the noncompliance prior to isolating the generating facilities. In emergency situations, when the Cumberland Valley Electric is unable to immediately isolate or cause the Member to isolate only the generating facility, Cumberland Valley Electric may isolate the Member's entire facility.
- 10) The Member shall agree that, without the prior written permission from Cumberland Valley Electric, no changes shall be made to the generating facility as initially approved. Increases in generating facility capacity will require a new "Application for Interconnection and Net Metering" which will be evaluated on the same basis as any other new application. Repair and replacement of existing generating facility components with like components that meet UL 1741 certification requirements for Level 1 facilities and not resulting in increases in generating facility capacity is allowed without approval.

DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	_
f(1) = 1	PUBLIC SERVICE COMMISSION
ISSUED BY Le Hugh TITLE Pres	dent & Chief Ore Kutiker Of Ciden
	EFFECTIVE
Issued by authority of an Order of the Public Service Commission	of Kentucky in 4/8/2009
Case No. 2008-00169 Dated January 8, 2009	PURSUANT TO 807 KAR 5:011
	SECTION 9 (1)
	$\wedge \parallel \cap \varOmega$
	By My Albert
	Executive Director

	FOR ENTIRE TERRITORY SERVED
	P.S.C
Cumberland Valley Electric	Original Sheet No.

11) To the extent permitted by law, the Member shall protect, indemnify, and hold harmless Cumberland Valley Electric and its directors, officers, employees, agents, representatives and contractors against and from all loss, claims, actions or suits, including costs and attorneys fees, for or on account of any injury or death of persons or damage to property caused by the Member or the Member's employees, agents, representatives and contractors in tampering with, repairing, maintaining, or operating the Member's generating facility or any related equipment or any facilities owned by Cumberland Valley Electric except where such injury, death or damage was caused or contributed to by the fault or negligence of Cumberland Valley Electric or its employees, agents, representatives, or contractors.

The liability of Cumberland Valley Electric to the Member for injury to person and property shall be governed by the tariff(s) for the class of service under which the Member is taking service.

- 12) The Member shall maintain general liability insurance coverage (through a standard homeowner's, commercial, or other policy) for both Level 1 and Level 2 generating facilities. The Member shall, upon request, provide Cumberland Valley Electric with proof of such insurance at the time that application is made for net metering.
- 13) By entering into an Interconnection Agreement, or by inspection, if any, or by non-rejection, or by approval, or in any other way, Cumberland Valley Electric does not give any warranty, express or implied, as to the adequacy, safety, compliance with applicable codes or requirements, or as to any other characteristics, of the generating facility equipment, controls, and protective relays and equipment.
- 14) A Member's generating facility is transferable to other persons or service locations only after notification to Cumberland Valley Electric has been made and verification that the installation is in compliance with this tariff. Upon written notification that an approved generating facility is being transferred to another person, member, or location, Cumberland Valley Electric will verify that the installation is in compliance with this tariff and provide written notification to the member(s) within 20 business days. If the installation is no longer in compliance with this tariff, Cumberland Valley Electric will notify the Member in writing and list what must be done to place the facility in compliance.

DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	
	PUBLIC SERVICE COMMISSION
ISSUED BY Lea Hunder TITLE Pres	dent & Chief Executive Officer
	EFFECTIVE
Issued by authority of an Order of the Public Service Commission Case No. 2008-00169 Dated January 8, 2009	
	SECTION 9 (1)
	By By Executive Director

12.5

Cumberland Valley Electric

15) The Member shall retain any and all Renewable Energy Credits (RECs) that may be generated by their generating facility.

EFFECTIVE TERM AND TERMINATION RIGHTS

1-07

This Agreement becomes effective when executed by both parties and shall continue in effect until terminated. This Agreement may be terminated as follows: (a) The Member may terminate this Agreement at any time by giving Cumberland Valley Electric at least sixty (60) days' written notice; (b) Cumberland Valley Electric may terminate upon failure by the Member to continue ongoing operation of the generating facility; (c) either party may terminate by giving the other party at least thirty (30) days prior written notice that the other party is in default of any of the terms and conditions of the Agreement or the Rules or any rate schedule, tariff, regulation, contract, or policy of Cumberland Valley Electric, so long as the notice specifies the basis for termination and there is opportunity to cure the default; (d) Cumberland Valley Electric may terminate by giving the Member at least thirty (30) days notice in the event that there is a material change in an applicable law, regulation or statute affecting this Agreement or which renders the system out of compliance with the new law or statute.

	PUBLIC SERVICE COMMISSION
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 200	OF KENTUCKY
	EFFECTIVE
ISSUED BY Led Hugter TITLE Pres	ident & Chief Executive Officer PURSUANT TO 807 KAR 5:011
Issued by authority of an Order of the Public Service Commissio	of Kentucky in SECTION 9 (1)
Case No. 2008-00169 Dated January 8, 2009	By H Deem Executive Director

	FO	R ENTIRE TERRITORY SERVED
Cumberland V	/alley Electric	P.S.C Original Sheet No
true, and I agree to abide	the best of my knowledge, all of the info e by all the Terms and Conditions included umberland Valley Electric's Net Metering	l in this Application for Interconnection
Member Signature	Date	
Title		
	COOPERATIVE APPROVAL SE	ECTION
	a Cooperative representative, Application f provisions contained in this Application an	
Cooperative inspection	and witness test: Required	Waived
business days o witness test w generating facil Unless indicated and witness te generating facil Call Pre-Inspection operation If inspection an installation is co	nd witness test is required, the Member of completion of the generating facility institution of the generating facility institution or as otherwise agreed to delow, the Member may not operate the set is successfully completed. Additional lity until all other terms and conditions in theto schedule an inspect conal testing not to exceed two hours: ad witness test is waived, operation of the generations to Application Information: Clarifications to Application Information: None As specified here:	tallation and schedule an inspection and business days of completion of the by the Cooperative and the Member. generating facility until such inspection ly, the Member may not operate the he Application have been met. tion and witness test. Allowed Not Allowed generating facility may begin when
Approved by:	Date:	
Printed Name:	Title:	PUBLIC SERVICE COMMISSION OF KENTUCKY EFFECTIVE
	2, 2009 DATE EFFECTIVE: <u>April 8, 2009</u>	
ISSUED BY Led	Hugh TITLE Presi	lent & Chief Evening Nffiel
	n Order of the Public Service Commission	

FOR ENTIRE	TERRITORY SERVED
	P.S.C
	Original Sheet No.

LEVEL 2

Application For Interconnection And Net Metering

Cumberland Valley Electric

Use this Application form when generating facility is not inverter-based or is not certified by a nationally recognized testing laboratory to meet the requirements of UL 1741 or does not meet any of the additional conditions under Level 1.

Submit this Application (along with an application fee of \$100) to:

Cooperative name and address

If you have questions regarding this Application or its status, contact the Cooperative at:

Cooperative Phone #, email

Member Name: _____ Account Number:

Type of Generator:

Power Source:

Member Address:

Total Generating Capacity of Generating Facility:

Solar

Inverter-Based

Wind

Project Contact Person:

Phone No.: ______ Email Address (Optional): _____

Provide names and contact information for other contractors, installers, or engineering firms involved in the design and installation of the generating facilities:

Adequate documentation and information must be submitted with this application to be considered complete. Typically this should include the following:

Hydro

Synchronous

Biogas

Induction

Biomass

DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	- PUBLIC SERVICE COMMISSION - OF KENTUCKY
	EFFECTIVE
ISSUED BY Jed Hungton TITLE Pres	dent & Chief Executive Officer PURSUANT TO 807 KAR 5:011
Issued by authority of an Order of the Public Service Commission	of Kentucky ir SECTION 9 (1)
Case No. 2008-00169 Dated January 8, 2009	$M \cap Q$
	By W Wager
	Executive Director

· · · · · · · · · · · · · · · · · · ·	FOR ENTIRE TERRITORY SERVED
	P.S.C
Cumberland Valley Electric	Original Sheet No.

- 1. Single-line diagram of the member's system showing all electrical equipment from the generator to the point of interconnection with the Cooperative's distribution system, including generators, transformers, switchgear, switches, breakers, fuses, voltage transformers, current transformers, wire sizes, equipment ratings, and transformer connections.
- 2. Control drawings for relays and breakers.
- 3. Site Plans showing the physical location of major equipment.
- 4. Relevant ratings of equipment. Transformer information should include capacity ratings, voltage ratings, winding arrangements, and impedance.
- 5. If protective relays are used, settings applicable to the interconnection protection. If programmable relays are used, a description of how the relay is programmed to operate as applicable to interconnection protection.
- 6. A description of how the generator system will be operated including all modes of operation.
- 7. For inverters, the manufacturer name, model number, and AC power rating. For certified inverters, attach documentation showing that inverter is certified by a nationally recognized testing laboratory to meet the requirements of UL1741.
- 8. For synchronous generators, manufacturer and model number, nameplate ratings, and impedance data (Xd, X'd, & X"d).
- 9. For induction generators, manufacturer and model number, nameplate ratings, and locked rotor current.

Member Signature:

Date:	

	PUBLIC SERVICE COMMISSION
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 200	OF KENTUCKY
-f(1) - 1	EFFECTIVE
ISSUED BY Jed Hundra TITLE Pres	dent & Chief Exect/6/2009ficer
9-1	PURSUANT TO 807 KAR 5:011
Issued by authority of an Order of the Public Service Commission	of Kentucky in SECTION 9 (1)
Case No. 2008-00169 Dated January 8, 2009	By W Director

LEVEL 2 INTERCONNECTION AGREEMENT

 THIS INTERCONNECTION AGREEMENT (Agreement) is made and entered into this

 day of
 ______, 20___, by and between

 (Cooperative), and
 ______(Member). Cooperative and Member are hereinafter

 sometimes referred to individually as "Party" or collectively as "Parties".

WITNESSETH:

WHEREAS, Member is installing, or has installed, generating equipment, controls, and protective relays and equipment (Generating Facility) used to interconnect and operate in parallel with Cooperative's electric system, which Generating Facility is more fully described in Exhibit A, attached hereto and incorporated herein by this Agreement, and as follows:

Location: _____

Generator Size and Type:

NOW, THEREFORE, in consideration thereof, Member and Cooperative agree as follows:

Cooperative agrees to allow the Member to interconnect and operate the Generating Facility in parallel with the Cooperative's electric system and the Member agrees to abide by Cooperative's Net Metering Tariff and all the Terms and Conditions listed in this Agreement including any additional conditions listed in Exhibit A.

TERMS AND CONDITIONS:

 Cumberland Valley Electric shall provide the Member net metering services, without charge for standard metering equipment, through a standard kilowatt-hour metering system capable of measuring the flow of electricity in two (2) directions. If the Member requests any additional meter or meters or distribution upgrades are needed to monitor the flow in each direction, such installations shall be at the Member's expense.

	DATE OF ISSUE <u>April 2, 2009</u> , DATE EFFECTIVE: <u>April 8, 2009</u> ISSUED BY <u>Lead Hungt</u> TITLE <u>Press</u> Issued by authority of an Order of the Public Service Commission Case No. <u>2008-00169</u> Dated <u>January 8, 2009</u>	OF KENTUCKY EFFECTIVE dent & Chief Executive Officer
--	--	--

•	FOR ENTIRE TERRITORY SERVED
	P.S.C
Cumberland Valley Electric	Original Sheet No.

- 2) The Member shall install, operate, and maintain, at the Member's sole cost and expense, any control, protective, or other equipment on the Member's system required by Cumberland Valley Electric's technical interconnection requirements based on IEEE 1547, the NEC, accredited testing laboratories such as Underwriters Laboratories, and the manufacturer's suggested practices for safe, efficient and reliable operation of the generating facility in parallel with Cumberland Valley Electric's electric system. The Member shall bear full responsibility for the installation, maintenance and safe operation of the generating facility. Upon reasonable request from Cumberland Valley Electric, the Member shall demonstrate generating facility compliance.
- 3) The generating facility shall comply with, and the Member shall represent and warrant its compliance with: (a) any applicable safety and power quality standards established by IEEE and accredited testing laboratories such as Underwriters Laboratories; (b) the NEC as may be revised from time to time; (c) Cumberland Valley Electric's rules, regulations, and Service Regulations as contained in Cumberland Valley Electric's Retail Electric Tariff as may be revised from time to time with the approval of the Kentucky Public Service Commission (Commission); (d) the rules and regulations of the Commission, as such rules and regulations may be revised from time to time by the Commission; and (e) all other applicable local, state, and federal codes and laws, as the same may be in effect from time to time. Where required by law, the Member shall pass an electrical inspection of the generating facility by a local authority having jurisdiction over the installation.
- 4) Any changes or additions to Cumberland Valley Electric's system required to accommodate the generating facility shall be considered excess facilities. The Member shall agree to pay Cumberland Valley Electric for actual costs incurred for all such excess facilities prior to construction.
- 5) The Member shall operate the generating facility in such a manner as not to cause undue fluctuations in voltage, intermittent load characteristics or otherwise interfere with the operation of Cumberland Valley Electric's electric system. At all times when the generating facility is being operated in parallel with Cumberland Valley Electric's electric system, the Member shall operate the generating facility in such a manner that no adverse impacts will be produced thereby to the service quality rendered by Cumberland Valley Electric to any

DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 2009	PUBLIC SERVICE COMMISSION
f(1) = -	OF KENTUCKY
ISSUED BY Lod, Hungan TITLE Pres	dent & Chief Executive Officer 4/8/2009
Issued by authority of an Order of the Public Service Commission Case No. 2008-00169 Dated January 8, 2009	of Kentucky in SECTION 9 (1)
	MORA
	By W Maeier
	Executive Director

·	FOR ENTIRE TERRITORY SERVED
	P.S.C
Cumberland Valley Electric	Original Sheet No.

of its other members or to any electric system interconnected with Cumberland Valley Electric's electric system. The Member shall agree that the interconnection and operation of the generating facility is secondary to, and shall not interfere with, Cumberland Valley Electric's ability to meet its primary responsibility of furnishing reasonably adequate service to its members.

- 6) The Member shall be responsible for protecting, at the Member's sole cost and expense, the generating facility from any condition or disturbance on Cumberland Valley Electric's electric system, including, but not limited to, voltage sags or swells, system faults, outages, loss of a single phase of supply, equipment failures, and lightning or switching surges, except that Cumberland Valley Electric shall be responsible for repair of damage caused to the generating facility resulting solely from the negligence or willful misconduct on the part of Cumberland Valley Electric.
- 7) After initial installation, Cumberland Valley Electric shall have the right to inspect and/or witness commissioning tests, as specified in the Level 1 or Level 2 Application and approval process. Following the initial testing and inspection of the generating facility and upon reasonable advance notice to the Member, Cumberland Valley Electric shall have access at reasonable times to the generating facility to perform reasonable on-site inspections to verify that the installation, maintenance, and operation of the generating facility comply with the requirements of this tariff.
- 8) For Level 1 and 2 generating facilities, an eligible Member shall furnish and install on the Member's side of the point of common coupling a safety disconnect switch which shall be capable of fully disconnecting the Member's energy generating equipment from Cumberland Valley Electric's electric service under the full rated conditions of the Member's generating facility. The external disconnect switch (EDS) shall be located adjacent to Cumberland Valley Electric's meters or the location of the EDS shall be noted by placing a sticker on the meter, and shall be of the visible break type in a metal enclosure which can be secured by a padlock. If the EDS is not located directly adjacent to the meter, the Member shall be responsible for ensuring that the location of the EDS is properly and legibly identified for so long as the generating facility is operational. The disconnect switch shall be accessible to Cumberland Valley Electric personnel at all times. Cumberland Valley Electric may waive the requirement for an EDS for a generating facility at its sole

DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 200	PUBLIC SERVICE COMMISSION
To (1) / - L	OF KENTUCKY
ISSUED BY ICA Hunden TITLE Pres	ident & Chief Excentive TOfficer
	4/8/2009
Issued by authority of an Order of the Public Service Commissio	n of Kentuk BouiaNT TO 807 KAR 5:011
Case No. 2008-00169 Dated January 8, 2009	SECTION 9 (1)
	NOP
	By Executive Director

ALL STREET

discretion, and on a case-by-case basis, upon review of the generating facility operating parameters and if permitted under Cumberland Valley Electric's safety and operating protocols.

- 9) Cumberland Valley Electric shall have the right and authority at Cumberland Valley Electric's sole discretion to isolate the generating facility or require the Member to discontinue operation of the generating facility if Cumberland Valley Electric believes that: (a) continued interconnection and parallel operation of the generating facility with Cumberland Valley Electric's electric system may create or contribute to a system emergency on either Cumberland Valley Electric's or the Member's electric system; (b) the generating facility is not in compliance with the requirements of this tariff, and the noncompliance adversely affects the safety, reliability, or power quality of Cumberland Valley Electric's electric system. In non-emergency situations, Cumberland Valley Electric shall give the Member notice of noncompliance including a description of the specific noncompliance condition and allow the Member a reasonable time to cure the noncompliance prior to isolating the generating facilities. In emergency situations, when Cumberland Valley Electric is unable to immediately isolate or cause the Member to isolate only the generating facility.
- 10) The Member shall agree that, without the prior written permission from Cumberland Valley Electric, no changes shall be made to the generating facility as initially approved. Increases in generating facility capacity will require a new "Application for Interconnection and Net Metering" which will be evaluated on the same basis as any other new application. Repair and replacement of existing generating facility components with like components that meet UL 1741 certification requirements for Level 1 facilities and not resulting in increases in generating facility capacity is allowed without approval.
- 11) To the extent permitted by law, the Member shall protect, indemnify, and hold harmless Cumberland Valley Electric and its directors, officers, employees, agents, representatives and contractors against and from all loss, claims, actions or suits, including costs and attorneys fees, for or on account of any injury or death of persons or damage to property caused by the Member or the Member's employees, agents, representatives and contractors in tampering with, repairing, maintaining, or operating the Member's generating facility or any related equipment or any facilities owned by Cumberland

	·
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 200	2 PUBLIC SERVICE COMMISSION
$- \left(1 \right) $	OF KENTUCKY
ISSUED BY Jed Hunder TITLE Pres	ident & Chief Executive Officer
	4/8/2009
Issued by authority of an Order of the Public Service Commissio	n of KeRILEISUANT TO 807 KAR 5:011
Case No. 2008-00169 Dated January 8, 2009	SECTION 9 (1)
	NOR
	By W Maeier
	Executive Director

Valley Electric except where such injury, death or damage was caused or contributed to by the fault or negligence of the Cumberland Valley Electric or its employees, agents, representatives, or contractors.

Cumberland Valley Electric

The liability of Cumberland Valley Electric to the Member for injury to person and property shall be governed by the tariff(s) for the class of service under which the Member is taking service.

- 12) The Member shall maintain general liability insurance coverage (through a standard homeowner's, commercial, or other policy) for both Level 1 and Level 2 generating facilities. The Member shall, upon request, provide Cumberland Valley Electric with proof of such insurance at the time that application is made for net metering.
- 13) By entering into an Interconnection Agreement, or by inspection, if any, or by non-rejection, or by approval, or in any other way, Cumberland Valley Electric does not give any warranty, express or implied, as to the adequacy, safety, compliance with applicable codes or requirements, or as to any other characteristics, of the generating facility equipment, controls, and protective relays and equipment.
- 14) A Member's generating facility is transferable to other persons or service locations only after notification to the Cumberland Valley Electric has been made and verification that the installation is in compliance with this tariff. Upon written notification that an approved generating facility is being transferred to another person, member, or location, Cumberland Valley Electric will verify that the installation is in compliance with this tariff and provide written notification to the member(s) within 20 business days. If the installation is no longer in compliance with this tariff, Cumberland Valley Electric will notify the Member in writing and list what must be done to place the facility in compliance.
- 15) The Member shall retain any and all Renewable Energy Credits (RECs) that may be generated by their generating facility.

DATE OF ISSUE <u>April 2, 2009</u> , DATE EFFECTIVE: <u>April 8, 200</u>	PUBLIC SERVICE COMMISSION
	OF KENTUCKY
ISSUED BY TITLE Pres	ident & Chief Executive Officer
	4/8/2009
Issued by authority of an Order of the Public Service Commissio	n of Kenturksuant TO 807 KAR 5:011
Case No. 2008-00169 Dated January 8, 2009	SECTION 9 (1)
	$\wedge \parallel \cap \varOmega$
	Will I Want
	By M Martin Director
	🖉 👔 🦞 😫 Kécutive Director

ور ۸

EFFECTIVE TERM AND TERMINATION RIGHTS

This Agreement becomes effective when executed by both parties and shall continue in effect until terminated. This Agreement may be terminated as follows: (a) The Member may terminate this Agreement at any time by giving Cumberland Valley Electric at least sixty (60) days' written notice; (b) Cumberland Valley Electric may terminate upon failure by the Member to continue ongoing operation of the generating facility; (c) either party may terminate by giving the other party at least thirty (30) days prior written notice that the other party is in default of any of the terms and conditions of the Agreement or the Rules or any rate schedule, tariff, regulation, contract, or policy of Cumberland Valley Electric, so long as the notice specifies the basis for termination and there is opportunity to cure the default; (d) Cumberland Valley Electric may terminate by giving the Member at least thirty (30) days notice in the event that there is a material change in an applicable law, regulation or statute affecting this Agreement or which renders the system out of compliance with the new law or statute.

IN WITNESS WHEREOF, the Parties have executed this Agreement, effective as of the date first above written.

•• COOPERATIVE NAME	MEMBER
Ву:	By:
Printed Name	Printed Name
Title:	Title:
DATE OF ISSUE <u>April 2, 2009</u> , DATE F	PUBLIC SERVICE COMMIS EFFECTIVE: April 8, 2009 OF KENTUCKY
ISSUED BY Lod Hang	

Original Sheet No.

Exhibit A

Upon application by a qualified Generating Facility, suitable drawings such as single lie diagrams and construction standards will be compiled, equipment/settings specified, and a detailed description of operation will be written.

When construction of, or upgrades to, utility facilities are required for interconnection, member shall agree to pay all costs associated with such construction or upgrade. These costs shall include actual cost of construction, the actual cost of any associated right-of-way acquisition and clearing, engineering costs, transportation costs and any other cost arising from or related to construction of required utility facilities. (See section entitled "TERMS AND CONDITIONS FOR INTERCONNECTION" of this tariff.)

A utility inspection and witness test will be coordinated between the prospective generating facility and Cumberland Valley Electric.

	PUBLIC SERVICE COMMISSION
DATE OF ISSUE April 2, 2009, DATE EFFECTIVE: April 8, 200	9 OF KENTUCKY
	EFFECTIVE
ISSUED BY TITLE Pres	ident & Chief Executive Officer PURSUANT TO 807 KAR 5:011
Issued by authority of an Order of the Public Service Commissio	n of Kentucky SECTION 9 (1)
Case No. 2008-00169 Dated January 8, 2009	
	By W MARIAN
	Executive Director